

HYER STANDARDS

Traffic Management

The Hansen Yuncken HYer Standards provide guidance on the minimum level of compliance expected for high risk activities on all projects.

Training & Competency



- Traffic management personnel must be appropriately licenced (as per state requirements):
 - Traffic Controllers
 - Traffic Management Implementer
 - Traffic Management Designer
- Personnel must be competent for the category of road that the temporary traffic management applies to

Traffic Management Plan (TMP)



- A Traffic Management Plan (TMP) is to be developed specific to the unique requirements for the project site
- TMPs must be developed by competent and qualified person(s) and based on a risk assessment
- Safe Work Method Statement (SWMS) must also be developed for all work that is carried out on, in or adjacent to a road in use by traffic other than pedestrians

Traffic Guidance Schemes (TGS)



- An on site risk assessment is to be conducted to ensure Traffic Guidance Scheme (TGS) is appropriate for the road environment
- The approvals for erection/removal of regulatory traffic control devices must be obtained from appropriate authority
- Signs and devices are to be erected, displayed, and removed in a defined order
- Records of dates and times temporary speed zones are active must be kept

Inspections



- Signs and devices must be inspected prior to installation to ensure they are in good condition and performance not impaired
- Daily inspections of TGS and signage arrangements must be recorded and kept
- The Traffic Guidance Scheme must be routinely monitored and maintained by a competent person to ensure its safe and efficient implementation

Pedestrian Management



- Pedestrian movement is to be controlled and managed when vehicles are entering and leaving site
- Members of public are to be excluded from all HY work areas
- Temporary ramp and access ways must:
 - Be provided for prams, strollers, wheelchairs and other mobility devices
 - Be inspected regularly for trip hazards and damage

On Site Traffic



- A Project Traffic Management Plan (PTMP) will document on site traffic management including:
 - Internal roadways and haul roads
 - Traffic signs and speed limits
 - Pedestrian paths and crossings
 - Site access and delivery processes
- The TMP developed by the traffic control organisation is to be included as an appendix to the PTMP



WORK DIFFERENTLY
WWW.HYWORKZONE.COM.AU



TRAFFIC MANAGEMENT PROCEDURE